

SoLID Cherenkov Prototype: Beam Test in Hall C (Spring 2020)

Simona Malace

June 8 2020

SoLID Collaboration Meeting


Outline

- pre-R&D goals
- Putting together the detector package
- Cosmics tests in the ESB
- Installation in Hall C
- Calibrations with a random trigger
- Beam data
- Beam data analysis
- Plan going forward

SoLID Cherenkov Pre-R&D Goals

→ From the first quarterly report:


Milestone	Objectives	Expected Completion Date	Status
1	Construction and delivery of Cherenkov tank to Jefferson Lab.	Early January 2020	Complete
2	Cosmic testing and installation into experimental hall.	Mid February 2020	Complete
3	Collection and analysis of low and high rate data with electronic summing-board.	End of Year 2020 (+2 Month Contingency)	In Progress
4	Collection and analysis of high rate data with MAROC electronics.	End of Year 2020 (+4 Month Contingency)	Not Started



SoLID Cherenkov Pre-R&D Goals

→ From the first quarterly report:

Milestone	Objectives	Expected Completion Date	Status
1	Construction and delivery of Cherenkov tank to Jefferson Lab.	Early January 2020	Complete
2	Cosmic testing and installation into experimental hall.	Mid February 2020	Complete
3	Collection and analysis of low and high rate data with electronic summing-board.	End of Year 2020 (+2 Month Contingency)	In Progress
4	Collection and analysis of high rate data with MAROC electronics.	End of Year 2020 (+4 Month Contingency)	Not Started




- Milestone 1: Temple U delivered the Cherenkov tank and the cradle to JLab at the very beginning of February

SoLID Cherenkov Pre-R&D Goals

→ From the first quarterly report:

Milestone	Objectives	Expected Completion Date	Status
1	Construction and delivery of Cherenkov tank to Jefferson Lab.	Early January 2020	Complete
2	Cosmic testing and installation into experimental hall.	Mid February 2020	Complete
3	Collection and analysis of low and high rate data with electronic summing-board.	End of Year 2020 (+2 Month Contingency)	In Progress
4	Collection and analysis of high rate data with MAROC electronics.	End of Year 2020 (+4 Month Contingency)	Not Started




- Milestone 1: Temple U delivered the Cherenkov tank and the cradle to JLab at the very beginning of February
- Milestone 2: during the month of February I assembled the detector package in the ESB for cosmics tests in preparation for the beam test; the test stand was then moved and installed in Hall C at the end of A1n

SoLID Cherenkov Pre-R&D Goals


→ From the first quarterly report:

Milestone	Objectives	Expected Completion Date	Status
1	Construction and delivery of Cherenkov tank to Jefferson Lab.	Early January 2020	Complete
2	Cosmic testing and installation into experimental hall.	Mid February 2020	Complete
3	Collection and analysis of low and high rate data with electronic summing-board.	End of Year 2020 (+2 Month Contingency)	In Progress
4	Collection and analysis of high rate data with MAROC electronics.	End of Year 2020 (+4 Month Contingency)	Not Started




- Milestone 1: Temple U delivered the Cherenkov tank and the cradle to JLab at the very beginning of February
- Milestone 2: during the month of February I assembled the detector package in the ESB for cosmics tests in preparation for the beam test; the test stand was then moved and installed in Hall C at the end of A1n
- Milestone 3: we collected data for about two days before the COVID-19 shutdown in the low rate configuration

Putting Together the Detector Package




Putting Together the Detector Package




→ Cherenkov tank (PVC) - 5 feet long and 1.25 feet diameter – and support (cradle) built at Temple U and delivered to JLab at the beginning of February

Putting Together the Detector Package



→ Box containing the 16 maPMTs tile on the electronics board



→ Cherenkov tank (PVC) - 5 feet long and 1.25 feet diameter – and support (cradle) built at Temple U and delivered to JLab at the beginning of February


I gain matched the maPMTs on the scope to get SPEs of 10 mV amplitude

Putting Together the Detector Package


→ Two scintillator planes flanking the Cherenkov tank

I sorted through bunch of paddles that were part of an old SLAC detector until I found 22 that were still usable (~ 1 inch width, 0.25 inch overlap between paddles; readout 0.5 inch Hamamatsu PMTs)

I calibrated the paddles/PMTs with a ^{60}Co source to get a signal of ~ 200 mV amplitude



→ Box containing the 16 maPMTs tile on the electronics board



→ Cherenkov tank (PVC) - 5 feet long and 1.25 feet diameter – and support (cradle) built at Temple U and delivered to JLab at the beginning of February

I gain matched the maPMTs on the scope to get SPEs of 10 mV amplitude

Putting Together the Detector Package

→ Two scintillator planes flanking the Cherenkov tank


I sorted through bunch of paddles that were part of an old SLAC detector until I found 22 that were still usable (~ 1 inch width, 0.25 inch overlap between paddles; readout 0.5 inch Hamamatsu PMTs)

I calibrated the paddles/PMTs with a ^{60}Co source to get a signal of ~ 200 mV amplitude


→ 9 calorimeter blocks (Shashlyk type) arranged in a 3 x 3 array; 4 locks are read by one PMT only (per block) while the remaining 6 are read by 4 PMTs (per block) – the blocks were gain matched with comics and later on with beam

→ Cherenkov tank (PVC) - 5 feet long and 1.25 feet diameter – and support (cradle) built at Temple U and delivered to JLab at the beginning of February

→ Box containing the 16 maPMTs tile on the electronics board




I gain matched the maPMTs on the scope to get SPEs of 10 mV amplitude




Tests with Cosmics in the ESB

Response of first plane of scintillators



Response of second plane of scintillators



→ The trigger was a three-fold coincidence between the 2 scintillator planes and the calorimeter

→ All detector channels (scintillator, calorimeter, maPMTs) are read with FADC250s

Installation in Hall C



Low rate configuration (~ 300 kHz rate on maPMTs):

→ On the SHMS side at ~ 105 deg, 17 feet away from the target

Installation in Hall C



Low rate configuration (~300 kHz rate on maPMTs):

→ On the SHMS side at ~ 105 deg, 17 feet away from the target

→ 100 meter signal cables run from the detectors to a patch panel behind the green wall and from there to the VME crate that houses the FADCs



Installation in Hall C



Low rate configuration (~ 300 kHz rate on maPMTs):

→ On the SHMS side at ~ 105 deg, 17 feet away from the target

→ 100 meter signal cables run from the detectors to a patch panel behind the green wall and from there to the VME crate that houses the FADCs

→ The HV to detector channels is provided via 16 bundle HV cables by a CAEN SY403 power supply



Installation in Hall C



Low rate configuration (~300 kHz rate on maPMTs):

- On the SHMS side at ~ 105 deg, 17 feet away from the target
- 100 meter signal cables run from the detectors to a patch panel behind the green wall and from there to the VME crate that houses the FADCs
- The HV to detector channels is provided via 16 bundle HV cables by a CAEN SY403 power supply
- The CO₂ gas pressure in the tank is maintained by a gas controller at 0.3 psi above 1 atm



Installation in Hall C



Low rate configuration (~300 kHz rate on maPMTs):

- On the SHMS side at ~ 105 deg, 17 feet away from the target
- 100 meter signal cables run from the detectors to a patch panel behind the green wall and from there to the VME crate that houses the FADCs
- The HV to detector channels is provided via 16 bundle HV cables by a CAEN SY403 power supply
- The CO₂ gas pressure in the tank is maintained by a gas controller at 0.3 psi above 1 atm
- All the power supplies are protected from radiation by a bunker



It took me one week (long days) to install everything in Hall C (thanks to Walter and the Hall C techs for helping out with craning and building the bunker)



Calibrations with a Random Trigger

→ After the installation in Hall C and before beam was sent into the Hall I refined the calibration of the maPMTs by taking data with a random trigger and detecting SPEs

SPE distributions for all 16 maPMTs (integrated charge)



maPMTs HV range: 1005 – 1170 V

Beam Data in the Low Rate Configuration

MODE 3 Beam Runs: Scintillator and Calorimeter Gain matching

Runs 113 – 134 (scintillator)

Runs 135 – 157 (calorimeter)


Beam Data in the Low Rate Configuration

MODE 3 Beam Runs: Scintillator and Calorimeter Gain matching


Runs 113 – 134 (scintillator)

Runs 135 – 157 (calorimeter)

Scintillator 2 plane charge integral



Scintillator 2 plane timing distributions



- Signal from minimum ionizing particles clearly seen in scintillator 2 plane when selecting the correct timing peak
- This is not the case with Scintillator 1 plane (swamped by background) – see back-up slides
- We ran with a 2-fold coincidence: calorimeter + scintillator 2 plane

Beam Data in the Low Rate Configuration


MODE 3 Beam Golden Runs

Runs 159 (C optics target), 161 (3He target)



Charge integral distributions from **all 16 maPMTs** (sums only)

Timing distributions from **all 16 maPMTs** (sums only)



Beam Data in the Low Rate Configuration

MODE 3 Beam Golden Runs

Runs 159 (C optics target), 161 (3He target)


MODE 1 Beam Golden Runs

Runs 158 (C optics target), 160 (3He target)

→ See Chao's talk

Charge integral distributions from **all 16 maPMTs** (sums only)

Timing distributions from **all 16 maPMTs** (sums only)



Beam Data in the Low Rate Configuration



MODE 3 Beam Golden Runs

Runs 159 (C optics target), 161 (3He target)

MODE 1 Beam Golden Runs


Runs 158 (C optics target), 160 (3He target)

→ See Chao's talk



Summary and Plan Going Forward


- We got enough data in the low rate configuration (SHMS side)
- Before beam comes to Hall C this Summer the Cherenkov test stand will be moved to the **high rate location** (between the HMS and beamline) – I have a LOT of work to do to make that happen



Summary and Plan Going Forward

- We got enough data in the low rate configuration (SHMS side)
- Before beam comes to Hall C this Summer the Cherenkov test stand will be moved to the **high rate location** (between the HMS and beamline) – I have a LOT of work to do to make that happen

- Mark the floor where the stand is now (we may go back to that location after the high-rate test)
- De-cable the signal cables for all 126 channels
- De-cable the HV
- Remove the bricks that protect the electronics box
- Remove the connections to the gas controller and to the low voltage power supply
- The test stand can then be craned to the HMS location – *Walter and Hall C techs*
- Pull more length for the signal cables – *with the Hall C techs*
- Cable the 126 channels (signal and HV)
- Find a place for the bunker and move it to the HMS side together with all the power supplies and the gas controller as well as the gas cylinder – *with Walter and the techs*
- Make connections to the gas controller and the HV and low V power supplies
- Test every channel from the patch panel behind the green wall (fix issues with one of the calorimeter channels of block 9; maPMT channel 22)
- Purge the tank and fill it with CO₂ at 0.3 psi above 1 atm
- Add back the shielding bricks
- Take maPMT data with a random trigger for sanity checks
- Take some cosmics data to sanity check the scintillator and calorimeter channels (the cradle will be sitting horizontally so...)
- Align the test stand with the target – *with Jack*




Summary and Plan Going Forward

- We got enough data in the low rate configuration (SHMS side)
- Before beam comes to Hall C this Summer the Cherenkov test stand will be moved to the high rate location (between the HMS and beamline) – I have a LOT of work to do to make that happen
- The stand will be at the HMS location for a short period only (before it starts to interfere with the current running experiment)
- After the quick high-rate running the stand will be moved out of the d2 experiment's way (back to the SHMS side to take data with other photon detectors) but ***work can happen opportunistically only***

All the tasks I listed on the previous slide have to be repeated

List of priorities regarding which photon detector to test first has been communicated to me by Zein-Eddine


- At the end of the Summer run the test stand will be removed from the hall and stored in the ESB



Backup

Beam Test in Hall C: Carbon Target


Trigger: coincidence between calorimeter and second plane of scintillators



Second Plane of scintillators

Beam Test in Hall C: Carbon Target


Trigger: coincidence between calorimeter and second plane of scintillators



First Plane of scintillators

Beam Test in Hall C: Carbon Target


Trigger: coincidence between calorimeter and second plane of scintillators



Calorimeter

Beam Test in Hall C: Carbon Target


Trigger: coincidence between calorimeter and second plane of scintillators



maPMTs - SUMS

Beam Test in Hall C: Carbon Target


Trigger: coincidence between calorimeter and second plane of scintillators



maPMTs - QUADS

Beam Test in Hall C: Carbon Target

Trigger: coincidence between calorimeter and second plane of scintillators



Blue: timing cut to select spe

Green: timing cut to hopefully select multiple photoelectrons

Pink: almost no timing cut

maPMTs - QUADS

I also analyzed the 3He run (not shown here)